GENT
by Honeywell

Technical Bulletin	TB 10032

To: System Integrators, Novar Gent Services	Date: 20/07/2004
	Status: Active
	Type: Gent/SI

Product – Part affected:
Vigilon commissioning Tool & S3 sounders

Details:
When using the soft start feature on S3 sounders the sounders start at the defined start volume but do not increase to the max volume

Action:
If the increment value is set to 0 then there can be no increase in volume and the device will continue to sound at the start volume. Ensure that the increment value is set between 1 & 10.

The 0 increment option is going to be removed from the commissioning tool in the next version to prevent this mistake from occurring.

Name: Peter Dodge