GENT
by Honeywell

Technical Bulletin	TB 10048

To: System Integrators, Novar Gent Services	Date: 24/02/2005
	Status: Active
	Type: Gent/SI

Product – Part affected:
Commissioning tool V1.18

Details:
Certain sites have been experiencing problems with Commissioning tool V1.18. The following problems have been reported after using the commissioning tool. S3 sounders coming up with memory corrupts. The loss of sectoring for sector 1 loop 1. Error 13 messages appearing during upload.

Action:
These issues are currently being investigated. At the moment we are not sure if they are site related or commissioning tool related. As a precaution we would recommend that any work carried out with Commissioning tool V1.18 is checked once uploaded and that if work is being carried out on none S4 site the use of commissioning tool V1.16 would be prudent until this issue is fully investigated.

An update on this issue will be out no later than 4th March

Name: Peter Dodge