GENT
by Honeywell

Technical Bulletin	TB 10080

To: System Integrators, Novar Gent Services	Date: 03/01/2006
	Status: Active
	Type: Gent/SI

Product – Part affected:
Problems smoke testing S4 devices

Details:
The following changes have been made in V3.92 and V4.32 of the MCC
In test and commissioning mode the S4 optical channel is far easier to activate.
In test mode you can change to auto silences alarms and resets. Test mode will only allow you to test sounders, not delay blocks, command builds or master sectoring.

If you use commissioning mode (free blocks need to be on for EN) then you can test the entire cause and effect.

Action:
Make sure engineers are aware of theses changes.

Name: Peter Dodge