GENT
by Honeywell

Technical Bulletin

TB:10211 I February 2016

Product parts affected

Commissioning tool v1.32

Details



A new commissioning tool v1.32 has now been released.

Enhancements:

- Only uses token bank 0 on LCC 3.70/4.10 or lower (these version did not have token bank 1&2)
- Improved device configuration screen load time
- Support for FAAST mains interface.
- Support of EN54 part 23 devices on old systems

Fixes:

- Were not able to alter sector assignment on 10th and above mains powered interface.
- Issues when inserting Plexus MCP (wireless devices)
- VAD devices FAB/SAB mapping not always displayed, in S4 page.
- Not able to turn off VAD strobe monitoring (low level flash every 6h) [turning off background monitoring will now disable this as well]

Action

Engineers to upgrade to new version of tool as soon as possible.

Note:

This new tool will allow you to turn off the strobe function in the S4 page on a strobe only device. Once uploaded, the panel will show this as "invalid config" for that device.

Correcting the setting and uploading will resolve this issue.

Changes will be made in the next release of tool to prevent this from occurring.

For any further queries relating to this issue please contact Technical support on 01162462134 or email technical.services@honeywell.com